



August 6, 2026

WELL TEST AND INSPECTION REPORT

Property Address: 1069 County Road 14

A well inspection was conducted at the above-referenced property. This is a drilled well construction with a measured depth of 205 feet and a static level found at 9 feet at time of inspection. This well has a capacity of 300 gallons.

A flow test was performed over a period of time at a pumping rate of 6 gallons per minute while monitoring drawdown and recovery. It was determined that this well is currently making 4.5 gallons per minute at this time.

Water Quality Results:

Parameter	Treated Water
Iron	0
Sulfur	0
Hardness	0 gpg
pH	7.5
Total Dissolved Solids (TDS)*	170 ppm

Based on inspection findings please find our recommendations and remarks:

1. The existing pressure tank is in good working order.
2. The existing water softener and ultraviolet light disinfection system are in good working order.
3. The existing peroxide injection system is in good working order.
4. I would recommend replacing the conduit at the well head with proper electrical conduit.

If you have any questions regarding these results and remarks, please do not hesitate to contact me.

Thank you,
John Jeffrey, Owner/Operator

Well Contractor #7275

John Jeffery Well Testing and Consulting does not assume any liability for changes in quality or quantity from the date of this report forward.